

QUATATION for the construction of School in
SIRAGU MONTESSORI SCHOOL, PALAVEDU VILLAGE
For MADRAS STRELING ROUND TABLE 123 & LC 63 .

24.09.15

Structure : R.C.C. framed structure as per drawing .
All ISI specified TMT rods and
53 Grade OPC (available in market).
Maha sakthi or Birla sakthi

Masonry work : 9" Solid blocks work for outer wall and 4"
Solid block wall for internal walls as per drawing in 1:6
C.M.

Height : All floors - 10Ft

Flooring: Cement Flooring 1:3

Doors & Windows: MS doors, windows & black board in each
classroom.


Painting :

Premium Waterproof Asian Cement paints to be provided for
Internal and external walls , Premium Gloss Enamel paint
for grills and doors.

Proposed to construct 5 classroom & headroom with
approximate area of 2506 sqft.

2506sqft @ Rs 1000/sqft = Rs 25,06,000/--

(Rupees Twenty Five Lakhs Six Thousand only)


 Thanking You
K. VENKITACHALAM, B.E (Civil).
Civil Engineer & Building Contractor

Class 1 Licensed Surveyor, Corporation of Chennai, No.98
Regd. Income Tax Valuer No C-1/151/1990

KRISHNA

#3, Shenoy Road, Nungambakkam, Chennai-600 034.
Ph: 28 3283, Cell 9841082628

E-mail : k_venkitachalam@hotmail.com



Yours Faithfully
S.Vasudevan