



EDUCATION AND SPORTS DEPARTMENT

Plot 47 – 55, Arua Avenue
www.aruacity.go.ug
+256 772 644368

P. O. Box 27, Arua
info@aruacity.go.ug
+256 774502797

OUR REF: ED/ACC/209/7

28th November 2025

The Executive Director
World Action Fund
P.O Box 340625
ARUA

EMERGENCY REQUEST FOR RE-ROOFING OF CLASSROOM BLOCK AT EDIOFE BOYS' PRIMARY SCHOOL

Two classrooms in Ediofe Boys primary school has been deroofed. Each of the classroom has been accommodating 234 pupils are now without classroom accommodation. Currently the learners are studying under the trees. Ediofe boys' primary school is highly enrolled primary school in the city with pupil classroom ratio of 1:160. This means that there is no free space where the affected learners can be accommodated.

The purpose of this letter is to seek for support to have the classrooms roofed. The estimated material cost for the project is 20,392,050/= . Which is attached.

We look forward to your positive response to this request.

Thank you



Obiayi Ombere Raymond
CITY EDUCATION OFFICER

Cc: Mayor/Arua City
Cc: The City Town Clerk/Arua City
Cc: Secretary Social Services. /Arua City

MATERIAL SCHEDULE FOR ROOFING 2-CLASS ROOM BLOCKAT EDIOFFE
BOYS PS

S/NO	PARTICULAR	UNIT	QTY	RATE	AMOUNT
1	Time 6"x2" tie beam and rafters	Pcs	110	16,000	1,760,000
2	Time 4"x2" wall plate	Pcs	11	16,000	176,000
3	Timber 4"x2" struts and purlin	Pcs	160	11,000	1,760,000
4	Timber 9"x1" fascia board	Pcs	18	25,000	450,000
5	Roofing sheet gauge 28	Pcs	130	60,000	7,800,000
6	Ridge cape	Pcs	13	25,000	325,000
7	Wood preservative	Jerican	6	25,000	150,000
8	Hoop iron	rolls	3	110,000	330,000
	Assorted nails				
9	6"	Kg	35	5,000	175,000
10	4"	bag	1	240,000	240,000
11	3"	Kg	10	5,000	50,000
12	1.5"	Kg	25	6,000	150,000
13	Roofing nails	Kg	25	7,000	175,000
14	Rubber washer	pkts	20	8,000	160,000
15	Transport		1	150,000	150,000
16	Matrial cost				13,851,000
17	Labour		1	2,300,000	2,300,000
	Sub total 1				16,151,000
	Brick work and finishes				
18	Concrete Vents	pcs	55	2,000	110,000
19	Cement	bags	20	33,000	660,000
20	Bricks	trips	2	300,000	600,000
21	Sand	trips	2	200,000	400,000
22	Scaffolding		1	300,000	300,000
23	Labour		1	1,200,000	1,200,000
	Sub total 2				3,270,000
	SUMMARY				
	Sub total 1				16,151,000
	Sub total 2				3,270,000
	TOTAL				19,421,000
	Supervision 5%				971,050
	Grand total				20,392,050

CITY EDUCATION OFFICER
ARUA CITY
P.O. BOX 2000
ARUA CITY
Sig: 

28/11/2025